

## HEALTH PROMOTING SPOT

S.No	Items Name	Description with scope of work
1	Class room Details	Rooms dimensions may vary as different sites have different sizes of the rooms the quoted prices must be in SQFT as the selection of the complete scope of work would on turn key basis and all the items should be quoted in SQFT with all duties and taxes, transportations and delivery to the destination should be kept in mind no additional cost would be added in terms of transportation or installation, there are different sites in 4 districts of KPK.
2	Requirements	Complete renovation of the room which includes false ceiling, vinyl flooring wall flattening which includes wall putty, plaster paras, grinding and leveling of the walls and painting of the walls, electricity work, Glass work in the windows or ventilations in the room, complete wood work, Glass writing Boards and logos printing on the Glass.

## SCOPE OF WORKS

1	Ceiling	Complete false ceiling in the room by adjusting the beams faults in it, designing of the false ceiling with ideal lighting scheming in the roof as per requirement designing should be done in such a manner that it gives a better look
---	---------	--

## 2 Walls and wood Paint

All the four walls should be filled with wall putty and plaster to make them even for a better look grinding of the walls should be done to make the walls look flat and straight, then distemper should be done on the walls with premium quality material,

**(i.e Master, Berger, ICI Paints)**

three walls of the rooms should be in one color as per selection and one wall should be painted in different color as per requirement for a better look

All the notice boards pasted on the walls these boards should be painted in different colors for a better look the sizes of the boards are:

1. 4x4 feet ( total of 4 Notice boards)
2. 6x4 Feet (1 honour board)

All the cupboards, windows and doors should be painted in white color.

The room entrance and the side walls with the windows of the rooms should be painted from outside as well.

### 3 Wood work

Complete boards plan in the room made with lassasni soft board sheets with notice board cloth on it and the border should be of 2 inches wooden framed.

1. 4x4 feet with the wooden borders of size 2 inches (total of 4 Notice boards)
2. 6x4 Feet (1 honour board with base of lassani sheet and soft board with notice board cloth on it and wooden frame to place the sliding pair of mirrors infrom of it) Red Color Lassani sheet
3. 2x 3 feet (1 board with 4 pockets of A4 size brochures) Blue color lasani sheet
4. 1.5 x 2 feet (1 board with 6 pockets of 3 folds brochures) Orange color Lasasni sheet
5. 1 x 2 feet (1 box with 4 shleves in it for medicine) red color and glass with lock and magnet door closer to be attached in front of the shelves
6. Ventilators should be covered with the sheet to flat the walls if required.

### 4 Vanyl Flooring

Vanyl/ plastic sheet should be installed in the room as per actaul size and requirement and should be properly fixed with the bond

### 5 Glass work

- 1 writing booard of size 5x3 feet of 8 MM glass should be polihed and placed on the wall with 6 studs & one duster and marker gass shelf should be installed on the side of the writing board
2. two glass boards 8 mm of size 18 x18 inches each should be placed with 4 studs on above of the writing boards (**each should have logos laser printing of the health department and project**)
4. 5mm glasses with channels and runners to be insatalled on the honour board size of the board 6x4 feet
5. 5 mm glass with lock , magnet and door closer studs for first aid box should be installed. size (18x36 inches)
6. windows/ ventialtor 3 mm Glass to be replaced if found damaged on any of the sites

6 Fire Extinguisher

2 Fire extinguishers with instructions and user manual should be installed one with the principal office and one to be installed outside the health rooting spot room

7 Electricity Work

4 Energy savers of ( Osaka/ Tuff or equivalent brand) with holders and 2 ceiling fans of (Pak/ GFC/Roayl brands) to be installed in each class room original copper wiring, changing of switch boards and buttons ( china board of 8+2 buttons with 2 fan dimmers)with plastic box and duct pattis) as per requirement wiring ducts to be used for the installation of wires for the savers and fans points.